# **Navajo Tribal Utility Authority**

**Advanced Metering Infrastructure Project** 

### **Abstract**

The Navajo Tribal Utility Authority's (NTUA) Advanced Metering Infrastructure (AMI) project deploys 28,000 residential smart meters and supporting communications and information technologies. The project provides automated meter reading, improved outage detection and response, power quality monitoring, and tamper detection capabilities. The communications system relays customer electricity data to NTUA, where the new meter data management system helps NTUA leverage the data to better manage peak demand, which results in reduced system-wide capacity needs, electrical losses, and operations and maintenance costs.

### **Smart Grid Features**

**Communications infrastructure** includes radio networks (900-MHz system) and wireless carrier backhaul systems. The project deploys a head-end system that monitors and stores all data collected from the meters and relays the data to other enterprise systems that are integrated with the new AMI system, including billing and outage management.

Advanced metering infrastructure includes the deployment of 28,000 smart meters to NTUA's residential customers. The deployment also includes a new meter data management system. The new communications infrastructure and automated operations of the smart meters enable NTUA to reduce operating and maintenance costs and improve service reliability through faster outage detection and response.

### At-A-Glance

**Recipient: Navajo Tribal Utility Authority** 

State: Arizona, New Mexico, Utah

**NERC Region: Western Electricity Coordinating** 

Council

Total Budget: \$9,983,500 Federal Share: \$4,991,750

Project Type: Advanced Metering Infrastructure and

**Customer Systems** 

## Equipment

- 28.000 Smart Meters
- AMI Communication Systems
  - Meter Communications Network
  - Backhaul Communications
- Meter Data Management System

#### **Key Targeted Benefits**

- Reduced Meter Reading Costs
- Reduced Operating and Maintenance Costs
- Improved Electric Service Reliability and Power Quality
- Reduced Electricity Costs for Customers
- Reduced Truck Fleet Fuel Usage
- Reduced Greenhouse Gas and Criteria Pollutant Emissions

### **Timeline**

| Key Milestones              | Target Dates |
|-----------------------------|--------------|
| AMI asset deployment begins | Q4 2010      |
| AMI asset deployment ends   | Q4 2012      |

### **Contact Information**

Srinivasa Venigalla, P.E. Electrical Planning Engineer Navajo Tribal Utility Authority e-mail: SrinivasaV@ntua.com

Recipient Team Website: www.ntua.com

