



Hazle Spindle, LLC Beacon Power 20 MW Flywheel Frequency Regulation Plant

Project Description

Hazle Spindle will design, build, and operate a flywheel energy storage frequency regulation plant at the Humboldt Industrial Park in Hazle Township, Pennsylvania. The plant will provide frequency regulation services to grid operator PJM Interconnection. The Beacon Power technology uses flywheels to recycle energy from the grid in response to changes in demand and grid frequency. When generated power exceeds load, the flywheels store the excess energy. When load increases, the flywheels return the energy to the grid. The flywheel system can respond nearly instantaneously to an independent system operator's control signal at a rate 100 times faster than traditional generation resources. The system does not burn fuel and has zero direct emissions. The Beacon Gen4 flywheel is designed to provide 100 kW of output and store 25 kWh of energy. Two hundred flywheels will be connected in parallel to provide 20 MW in capacity and can fully respond in less than 4 seconds. The plant can operate at 100% Depth of Discharge with no energy degradation over time and can do so for over 150,000 full charge/discharge cycles. The flywheels are built to last 20 years or more. Virtually no maintenance is required in the mechanical portion of the flywheel system. Flywheel technology has been successfully tested on live grids at scale power in New York and California. The technology achieved system availability of over 97 percent, higher than the average for conventional generators performing frequency regulation. It has been deployed at multi-megawatt scale under New England's Alternative Technologies pilot program, and a 20 MW plant in New York Independent System Operator (ISO) territory in Stephentown NY.

Goals/Objectives

- Demonstrate and speed the deployment of fast response flywheel-based frequency regulation
- Stimulate the international market demand for flywheel energy storage
- Quantify and verify the commercial viability and scalability of this Smart Grid energy storage technology
- Increase transmission capacity and reduce congestion

Key Milestones

- Site construction begins (April 2013)
- Plant commences operation (September 2013)
- Site construction complete (November 2013)
- Plant reaches full capacity (final flywheels installed) (June 2014)

Benefits

- Job creation
- Grid reliability improved
- Wind and solar power use increased
- Greenhouse gas emissions reduced
- Dependence on fossil fuel decreased
- Increase transmission capacity and reduce congestion



CONTACTS

Ronald Staubly
Project Manager
National Energy Technology Laboratory
3610 Collins Ferry Road
Morgantown, WV 26507-0880
304-285-4828
Ronald.Staubly@netl.doe.gov

Rob Rounds
Principal Investigator
Beacon Power
65 Middlesex Road
Tyngsboro, MA 01879-2041
978-661-2811
rounds@beaconpower.com

PARTNERS

PJM Interconnection
PPL Electric Utilities

PROJECT DURATION

1/1/2010–9/30/2015

BUDGET

Total Project Value
\$52,415,000

DOE/Non-DOE Share
\$24,063,978/\$28,351,022

EQUIPMENT

None Listed

DEMONSTRATION STATES

Pennsylvania

CID: OE0000200

*Managed by the National Energy Technology
Laboratory for the Office of Electricity
Delivery and Energy Reliability*