

# **EPRI Smart Grid Demonstration Host Site Project**

# FirstEnergy/JCP&L Host Site Overview/Update

#### **Integrated Distributed Energy Resources Management**



Joe Waligorski

Technical Manager – FE Technologies

**Eva Gardow** 

Project Manager – FE Technologies


**February 3, 2009** 

#### **Presentation Outline**

Slide Description	Slide #
JCP&L/FE Overview	3
FirstEnergy Integrated Grid Road Map	4
JCP&L/FE EPRI Host Demonstration Project	5
Direct Load Control, Integrated Platform	6
State Monitoring, Integrated Control Platform	7
Expanded Integration and Associated Benefits	8
JCP&L/FE, EPRI Project Management Tasks	9
JCP&L/FE Host Site Project Management Task Alignment	10
Operations Integration Due Diligence & Planning	11
Use Case Development Process	12
Integration of DER into FirstEnergy Systems	13
JCP&L/FE EPRI Project Participants	14
Status	15
Feedback	16



## JCP&L/FirstEnergy Overview




Rankings among Electric Utilities

Assets 9
Customers 5
Revenues 8
Market Cap 7

- » FE is a diversified energy company based in Akron, OH
- » JCP&L is one of FE's seven electric utility operating companies
- » Nation's 5th largest investor-owned electric system
- » JCP&L serves 1.1 million customers of 4.5 million FE customers
- » 128,000 miles of transmission & distribution lines
- Nearly \$12 billion in annual revenues and more than \$31 billion in assets



## FirstEnergy Integrated Grid Road Map



A FiretEnergy Company


### JCP&L/FE EPRI Host Site Demonstration Project

#### **Comprised of:**

- Integrated Control Platform and 8MW Direct Load Control pilot
- 15MW DLC Expansion
- 5MW Permanent Peak Load Shift program
- 3MW Electricity Storage program
- Distribution Sensors
- Other DER technologies

Project aligns with FirstEnergy IGCA Strategy

Project aligns with EPRI Smart Grid Strategy





### Direct Load Control, Integrated Control Platform

JCP&L/FE Host Site Project EPRI Smart Grid Demonstration

Integrated Control Platform and 8MW
Direct Load Control pilot

Integrated
Distributed Energy
Resources
Management
Integrated Control
Platform

Direct Load Control 8 MW Pilot

- Premise information viewed by Operator on user interface
  - Alarm triggers based on monitored device parameters
  - Individual & aggregated load information
  - Building temperature
- Local Grid Sensing and Control
  - Residential Load Controllers
  - Commercial & Industrial integration with energy management systems
- Load management verification via reports and audit logs
- Customized load control programs



### State Monitoring, Integrated Control Platform


JCP&L/FE Host Site Project EPRI Smart Grid Demonstration

Integrated Control Platform and 8MW
Direct Load Control pilot

Distribution Sensors

15MW DLC Expansion

- Monitor and visualize state transitions of individual devices
  - Line mounted sensors
- Action plans for state management
  - Operator controlled
  - Real time verifiable
- Customized verification reports





#### **Expanded Integration and Associated Benefits**

Integrated Control Platform and 8MW
Direct Load Control pilot

Distribution Sensors


15MW DLC Expansion

3MW Electricity Storage program

5MW Permanent Peak Load Shift program

Other *DER* technologies

JCP&L/FE Host Site Project EPRI Smart Grid Demonstration



- Condition-based monitoring and state estimation via enhanced platform capabilities
- System alarm coordination
- Automated condition response
- Integrated Electricity Storage
- Integrated Permanent Peak Load Shifting

# Integration Planning, Analysis and Testing

Methodologies and Standards Development
Performance Requirements and Use Case Development
Integration Activities, Testing, and Analysis



## JCP&L/FE, EPRI Project Management Tasks

	JCP&L/FE EPRI Smart Grid Demonstration Host Site Project
Task	Task Description
1	Project Planning and Objectives Setting
2	Equipment Deployment (Installation)
3	System Integration Activities
4	Monitoring and Performance Assessment
5	Performance and Integration Requirements
6	Benchmarking Project to Existing Methodologies and Standards
7	Develop Use Case Scenarios
8	Develop Business Case Scenarios
9	Tasks to Support System Use
10	Smart Grid Demo Project Analysis Activities



#### JCP&L/FE Host Site Demonstration Project Task Alignment

Project Planning and Objectives
Task 1

Physical Deployment, Integration and Testing Tasks 2, 3, 4

•Equipment Deployment
•Integrated Control Platform
Configuration &Deployment
•Lessons Learned

•Systems Integration Requirements
•Systems Integration Planning
•Integration Implementation

•Implementation Monitoring
•Performance Testing

Performance
Requirements, Use Case
Modeling and Analysis
Tasks 5, 6, 7, 8

 Performance and Integration Requirements
 Operations Integration Planning

•Benchmark Standards, Methodologies and Common Information Models (CIM) •Benchmark to IntelliGrid

Develop Operational Use Cases
 Develop Market Use Cases
 Align Use Cases with IntelliGrid

Develop Business Case Scenarios
 Performance Analysis
 Economic Analysis

Tasks to Support System Use Task 9

Smart Grid Project Analysis
Task 10



## Operations Integration Due Diligence & Planning

Meetings with JCP&L/FE and vendor teams to determine integration system performance requirements:

- Feasibility of system use to support distribution operations
- Development of performance requirements for operational scenarios (system capabilities, visualization tools)
- Develop underlying Use Cases for operational scenarios
- Develop Cost Benefit Analysis for each Use Case




### Use Case Development Process

- Integration of IntelliGrid Methodology into Project Framework
- Determine Operations and Planning Use Cases for Development
- Develop Data Collection and Verification Plan
- Conduct Testing and Use Case Model Analysis
- Refine Use Cases
- Develop Business Case and Cost Benefit Analysis
- Publish Final Analysis and Report



Integration of DER into JCP&L/FE Control and Communications Systems





# JCP&L/FE EPRI Smart Grid Host Site Project Participants

- EPRI
- JCP&L/FirstEnergy prime contractor
- BPL Global, Ltd. subcontractor
- Dynamic Energy Group subcontractor
- Distribution Sensor vendors
- Electricity Storage vendors
- Permanent Peak Load Shifting vendors
- Other DER vendors



#### **Status**

Milestone	Delivered
Launch Residential Deployed	9/08/08
1 <sup>st</sup> 1,000 customers Deployed	10/25/08
4,000 A/C units Deployed	1/31/09
Initial Communications Network Deployed	11/25/08
Final Network Deployed	3/13/09
Network Startup/Burn-in Complete	3/20/09
BPU Approval, Large Business Solicitation	10/22/08
Launch Large Business Solicitation	11/24/08
Large Business Solicitation Complete	2/28/09
BPU Approval, Small Business Solicitation	10/22/08
Launch Small Business Solicitation	12/05/08
Small Business Solicitation Complete	2/13/09
Form Stakeholder Teams to Focus Integration Efforts	2/11/09



#### Feedback Instructions

- On the phone, state your Name, Affiliation, and Question/Feedback
- To submit Questions or Feedback electronically, please email to Matt Wakefield: <a href="mailto:mwakefield@epri.com">mwakefield@epri.com</a> by Monday February 9<sup>th</sup>

#### Thank You!

